

rescue and training facility in Brooklyn, New York. Initial phase – foundation waterproofing. Originally specified "damp proofing" products could not be used due to very cold weather. Developer submitted BondTAC 1500 to the architect – Studio Gang Architects, and it was approved as a replacement product. The entire foundation was coated with two coats of BondTAC 1500, and one coat of BondTAC was applied to the back of the drainage board, which was then pressed to the coated cement of the foundation wall. The waterproofing was completed, and construction continued on schedule. The project would have been delayed 6-8 weeks due to the cold weather if BondTAC had not been available. As the project progresses, BondTAC will be used throughout multiple other sections of the structure, including wet rooms, showers, scuba training tank, and building façade.

